	Total	**9794.52**							
6	Carriage of Mixed Materials Page No. 186 Note PWD SR 2013-14			**Qty item no.6**			95.25	52.11	**4963.00**
	1st to2ndKM	5.75							
	2nd-5th KM	16.50							
	5th -10th KM	26.00							
		48.25							
	Area Weightage 8%	3.86							
	Total	**52.11**							
7	Removing B.S.Slab of drain and stacking etc., complete Page No. 28/ Item No. 5.32/ PWD SR 2013-14	**Sqm**							
	12th cross		1	130.00	0.90		117.00		
		Consider 60% Qty					70.20		
							70.20	50.11	**3518.00**
	Basic Rate	46.40							
	Add Area Weightage 8%	3.71							
	Total	**50.11**							
8	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2013-14)	Cum							
	12th cross		1	130.00	0.45	0.15	8.78		
							8.78	4211.38	**36955.00**
	Basic Rate	3973.00							
	Add Area Weightage 6%	238.38							
	Total	**4211.38**							
9	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2013-14)	Cum							
	12th cross		1	130.00	0.45	0.08	4.39		
	Kerb stone joints		1	130.00	0.45	0.08	4.39		
							8.78	4690.50	**41159.00**
	Basic Rate	4425.00							
	Add Area Weightage 6%	265.50							
	Total	**4690.50**							
11	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 28/ Item No.5.33/ PWD SR 2013-14	**Sqm**							
		Qty Vide Iteam No 7					**70.20**		
							70.20	70.04	**4917.00**
	Basic Rate	64.85							
	Add Area Weightage 8%	5.19							
	Total	**70.04**							